

M9-13

Labor shall be based on the following:

Construction

- Assemble in accordance to the Construction Specification Drawings and the specifications for construction
- Complete continuity of all jumper connections – Stirrup is called for separately by type and wire size
- Installation of all wildlife guards
- Associated labor for construction in existing line (i.e. switching, cover up, etc)

Removal

- Any labor necessary to prepare for removal (i.e. switching, cover up, etc.)
- Remove hotline clamp from stirrup
- Remove equipment and disassemble framing
- All Removed Material shall be returned to the District Storeroom in which the project is located

Replacement

- Any labor necessary to prepare for removal (i.e. switching, cover up, etc.)
- Remove hotline clamp then equipment and framing
- Installation of new units in accordance to Construction Specification Drawing and the specifications for construction
- Connect hotline clamp and jumper to stirrup
- Installation of all wildlife guards
- All Removed Material shall be returned to the District Storeroom in which the project is located